

Sterling Supplies - Black PVD Stainless Tactiles - Wet Sliptest KO130522-1

13 May 2022


Slip Resistance Classification of New Pedestrian Surfaces - AS4586:2013 Appendix A

| | |
|---------------------------------------|---|
| Date Tested: | 13 May 2022 |
| Test Report Number: | KO130522-1 |
| Client Name & Address: | Sterling Supplies - 28-34 Paraweena Drive Truganina Victoria 3029 |
| Test Site / Surface Tested : | Black PVD Stainless Tactiles - Applied to 300x300cm MDF Board |
| Sample Information : | Samples and Test Information Supplied by Client |
| Wet Pendulum Test carried out using : | Slider 96 (4S) Rubber slider |
| Any Variations to Standards | Variation of Standards only 1 Sample Available for testing |
| Testing Officer / Approved Signatory: | Kathryn Ording |
| Pendulum in use - Calibration Date : | #SK2072 - Wessex Portable Skid Tester (C : 07.05.21) |

Signature of Approved Signatory :



Test Results :

| Sample No. | Swing 1 | Swing 2 | Swing 3 | Swing 4 | Swing 5 | Mean BPN of last 3 swings : | SCV : | Surface Picture |
|------------|---------|---------|---------|---------|---------|-----------------------------|-------|---|
| Area 1 | 90 | 90 | 88 | 88 | 88 | 88 | N/A | |
| Area 2 | 90 | 90 | 88 | 88 | 88 | 88 | N/A | |
| Area 3 | 90 | 90 | 90 | 89 | 89 | 89 | N/A |  |

Variation to Standard Mean BPN Slip Resistance Value (SRV) 88

CLASSIFICATION using Slider 96 (4S Slider) P5 = > 54

Accredited for Compliance with ISO/IEC 17025. The information presented herein and on the Sliptest Report is copyright and is protected by copyright law, any reproduction of this information and test report except in full is prohibited. Sliptest Australia Pty. Ltd. performed this on site test with reference to the following Australian Standard testing criteria, of AS 4586:2013 Classification of new pedestrian surface materials. Appendix A - Wet Pendulum Test Method and Hand Book HB 198: 2014 with reference to AS/NZS 4663: 2004 Slip Resistance measurement of existing pedestrian surfaces and HB 197: 1999. These results do not account for Future Wear, Maintenance or Contamination of this surface once in-situ.

Page 1 of 1 - END OF REPORT